CITY OF TIGARD ENGINEERING DEPARTMENT

BID TABULATIONS for:

ASPEN RIDGE STORM DRAIN REPAIR 11876 SW ASPEN RIDGE DRIVE

Project No. 0469

		ENGI		ENGINEE	R'S ESTIMATE	SUNQUEST (SUNQUEST CONST. INC.		FISHER CONST.	
ITEM		BID	LINUT	UNIT	TOTAL	UNIT	TOTAL	UNIT	TOTAL	
NO.	DESCRIPTION	QUANTITY	UNIT	PRICE	AMOUNT	PRICE	AMOUNT	PRICE	AMOUNT	
1	MOBILIZATION	****	L.S.	****	\$1,500.00	****	\$2,977.00	****	\$2,000.00	
2	EROSION CONTROL	****	L.S.	****	\$300.00	****	\$220.00	****	\$1,000.00	
3	REMOVE & REPLACE TREES	3	EA.	\$150.00	\$450.00	\$220.00	\$660.00	\$800.00	\$2,400.00	
4	EASEMENT RESTORATION	****	L.S.	****	\$500.00	****	\$1,280.00	****	\$3,000.00	
5	TRENCH EXCAVATION & BACKFILL (0'-10')	60	L.F.	\$30.00	\$1,800.00	\$37.00	\$2,220.00	\$50.00	\$3,000.00	
6	REMOVE EXIST STORM SYSTEM	****	L.S.	****	\$500.00	\$320.00	\$320.00	****	\$1,600.00	
7	18" PVC	61	L.F.	\$60.00	\$3,660.00	\$16.55	\$1,009.55	\$25.00	\$1,525.00	
8	12" PVC	9	L.F.	\$50.00	\$450.00	\$11.11	\$99.99	\$20.00	\$180.00	
9	3/4"-0" CRUSHED ROCK, GRADED & COMPACTED	20	C.Y.	\$30.00	\$600.00	\$31.00	\$620.00	\$55.00	\$1,100.00	
10	CONNECT PIPE TO EXISTING AREA INLET	1	EA.	\$700.00	\$700.00	\$90.00	\$90.00	\$2,000.00	\$2,000.00	
11	CONNECT PIPE TO EXISTING MANHOLE	2	EA.	\$700.00	\$1,400.00	\$130.00	\$260.00	\$500.00	\$1,000.00	
		PROJECT TOTAL			\$11,860.00	=	\$9,756.54		\$18,805.00	