

## **NOTES:**

- 1. CONCRETE COMPRESSIVE STRENGTH SHALL BE A MINUMUM OF 3300 PSI AFTER 28 DAYS.
- 2. CURB JOINT SHALL BE TROWELED WITH A MIN 1/2" RADIUS ALONG BACK OF CURB.
- 3. EXPANSION & CONTRACTION JOINTS SHALL BE 1/2" PREMOLDED ASPHALT IMPREGNATED MATERIAL OR EQUAL EXTENDING FROM SUBGRADE TO FINISH GRADE.
- 4. 6" X 6" 10 GA MESH REQUIRED FOR COMMERCIAL DRIVEWAYS ONLY.

