



VAULT SPECIFICATIONS

SIZE	MFG.
1"	UTILITY VAULT 3030-LA (OR EQUAL)
1-1/2" - 2"	UTILITY VAULT 3642-PUT (OR EQUAL)

REDUCED PRESSURE BACKFLOW PREVENTER FEBCO MODEL 825Y OR EQUAL

PLAN

SLOPE EARTH AWAY FROM VAULT IN BERM AREA

12' MIN ABOVE FINISH GRADE

CURB

FINISH GRADE

CONCRETE PAD

ELEVATION

ADEQUATE DRAIN TO DAYLIGHT (SEE DETAIL NO. 557)

INSTALLATION SHOWN IS ONLY A SUGGESTION.

1. DOUBLE CHECK TO BE LOCATED DIRECTLY BEHIND WATER METER.
2. BRASS, STAINLESS, OR PLASTIC PLUGS TO BE INSTALLED IN TEST COCKS IF BELOW GROUND INSTALLATION.
3. DISTANCE FROM BOTTOM OF DEVICE TO FINISH GRADE, FREEZE PROTECTION, AND CLEARANCE FOR TESTING AND REPAIR ARE THE MAJOR CONSIDERATIONS FOR INSTALLATION.



ENGINEERING DEPARTMENT
13125 S.W. HALL BLVD.
TIGARD, OREGON 97223
VOICE: (503) 639-4171
FAX: (503) 684-7297

APPROVED BY:
AGUSTIN P. DUENAS

CITY ENGINEER

MARCH 1998

APPROVAL DATE

**REDUCED PRESSURE
BACKFLOW ASSEMBLY**

NO SCALE

DWG. NO.

555